# REQUEST FOR PROPOSALS
# Oceanspray Duplexes | Sanitary Sewer Replacement

**Housing Authority of Lincoln County (HALC)**

Project location: Oceanspray Duplexes, Newport, Oregon | 30 residential units across three city blocks

Issue date: 11/4/2026

Proposal deadline: 11/25/2026

Site visit scheduling:

Dan Butler, Asset and Development Manager
dbutler@housinglincolncountyor.gov
541-265-5326 Ext 312

## 1. Invitation and project overview

HALC invites qualified contractors to submit proposals to construct a replacement sanitary sewer collection system serving the 30 units at Oceanspray Duplexes. The new system shall be installed substantially parallel to, and independently of, the existing sewer system, so that existing service remains in operation during construction. Units shall be switched over one at a time, with coordinated outages kept to the shortest practicable duration. The contractor shall furnish all labor, materials, supervision, equipment, traffic control, testing, restoration, and incidentals required for a complete, operational system.

## 2. Scope of work

### 2.1 Preconstruction, investigation and coordination

- Confirm existing sewer routes, invert elevations, slopes, manholes, service laterals, public/private ownership boundaries, and locations of water, storm, gas, electric and communications utilities. Perform utility locates, potholing and other investigations as needed. The contractor shall retain an Oregon-licensed professional civil engineer to prepare and seal complete civil construction plans for the replacement system, including survey and utility verification as needed, pipe alignments and profiles, invert elevations and slopes, manholes, unit laterals and cleanouts, crossings, phased cutovers, code-compliant abandonment and restoration details. The contractor shall submit plans for all required agency review and approval, provide HALC with approved PDF and editable/record copies, and obtain HALC approval before construction begins.
- Develop a construction sequence showing new main installation, each unit cutover, testing, abandonment, access arrangements and restoration. Coordinate with HALC, residents, City of Newport and other affected authorities or utility owners.
- Provide necessary construction staking, erosion/sediment control, excavation safety plans, trench protection and dewatering measures as required by actual site conditions and applicable permits.

### 2.2 New gravity sanitary collection system

- Excavate and install new 4-inch, 6-inch and 8-inch sewer piping as needed, or approved engineered alternatives, with appropriate bedding, backfill, compaction, grade, cleanouts, fittings, connections and protection. Pipe material and installation shall comply with approved plans and applicable codes.
- Furnish and install manholes at required locations, depths and sizes, including watertight connections, channels, covers and surface adjustments. Confirm final number, depths, rim/invert elevations and connections in approved plans.
- Provide necessary connections to the receiving sewer system subject to approval by the authority having jurisdiction; avoid any unauthorized discharge or disruption of active public sewer infrastructure.

### 2.3 Phased connection of 30 occupied units

- Keep existing sewer service operational while the replacement piping is constructed and tested. Do not disconnect a unit until its new service connection is ready for immediate switchover.
- Connect each of the 30 units individually to the replacement sewer and provide a new code-compliant, accessible cleanout at each unit service as needed. Verify proper flow and watertight connections before returning each unit to normal operation.
- Give HALC advance written notice of each planned interruption; schedule work with HALC and affected residents, maintain safe access and sanitation, and immediately remedy any unintended sewer outage or backup. No simultaneous building-wide cutover without prior written authorization.

### 2.4 Abandonment of existing sanitary sewer lines per code

Following successful cutover, inspection and acceptance of the replacement services, the contractor shall permanently disconnect and abandon the superseded sanitary sewer mains, laterals, manholes and appurtenances in accordance with all applicable City of Newport requirements, Oregon plumbing and construction codes, utility-owner standards, approved plans, and permit conditions. Abandonment shall prevent future sewage flow, infiltration, exfiltration, settlement, collapse and inadvertent reconnection.

- Obtain approval of the proposed abandonment method from the jurisdiction and utility owner before performing abandonment work. Identify sections to be removed versus abandoned in place.
- For pipes approved to remain in place, properly isolate and seal or cap every open end and former connection with approved watertight materials; fill/grout abandoned pipe segments if required by code, permit, jurisdiction or site conditions. Do not presume abandonment in place is permitted everywhere.
- Remove, fill, grout, seal, or adjust obsolete manholes and other structures as directed by approved plans and the authority having jurisdiction; eliminate unsafe voids and potential future settlement.
- Where pipe removal is required, excavate, remove and legally dispose of the old materials, then backfill and compact the excavation to the specified standards.
- Do not abandon any section until all active services on that section have been transferred and verified; submit an abandonment log and as-built plan showing retired segments, caps, filled portions, removed structures and locations.

### 2.5 Excavation, restoration and protection

- Perform trench excavation, shoring/sloping, dewatering as needed, handling of unsuitable material, imported bedding/backfill, compaction testing and safe protection of adjoining buildings, utilities and existing improvements.

- The contractor is solely responsible for identifying, applying for, obtaining, paying for, maintaining and closing out all permits and approvals required for design and construction, including City of Newport, street/right-of-way, excavation, sewer connection, erosion control and traffic control approvals as applicable. Provide HALC copies of all approved plans, issued permits and final signoffs. Perform no regulated work before the applicable approval is issued. Provide approved traffic and pedestrian controls and preserve emergency access.
- Sawcut and replace disturbed asphalt, concrete, curbs, sidewalks, driveways and parking surfaces to match existing serviceability and meet jurisdictional restoration requirements; restore landscaping and drainage features impacted by the work.
- Protect all stormwater conveyance, potable water lines and other utilities. Repair any damage caused by construction at no additional cost to HALC except as otherwise addressed by an approved change order.

### 2.6 Testing, commissioning and closeout

- Conduct required sewer line and manhole inspections and testing, including leakage/pressure or air testing, deflection testing, CCTV inspections and compaction testing where required by governing standards and approved plans. Correct failed work and retest.
- Provide final inspections and approvals, verified record drawings/as-builts, test results, permit signoffs, warranties, abandonment documentation and a final site cleanup.

## 3. Contractor qualifications and legal requirements

Proposers shall hold appropriate Oregon Construction Contractors Board licensing and all endorsements required for the work; use properly licensed trade subcontractors as applicable; maintain required insurance and bonding; comply with OSHA excavation and confined-space requirements, Oregon utility notification rules, and all applicable local, state and federal laws.

DAVIS-BACON WAGE RATE PROJECT. This project is subject to applicable Davis-Bacon and Related Acts prevailing wage requirements. The contractor and all covered subcontractors shall pay not less than the applicable basic hourly wage rates and fringe benefits for work actually performed; maintain and submit certified payrolls, classifications and other compliance records as required; post applicable notices and the wage determination; and comply with all required federal labor standards clauses, including 29 CFR Part 5 as applicable. The applicable Lincoln County, Oregon Heavy Construction wage determination is OR20260072, Modification 1, published May 18, 2026 (see Appendix A). Bidders shall account for these obligations in their pricing.

## 4. Proposal content

- Company qualifications, current Oregon CCB license, responsible project manager, and relevant qualifications and references for occupied-residential sanitary sewer replacement work.
- Proposed method and construction sequence, including individual unit cutovers, planned interruption durations, resident notification procedure, safety and access controls.
- Itemized lump-sum proposal with clear allowances or unit prices for unforeseen conditions, including rock, unsuitable soils, groundwater, changed pipe lengths and restoration quantities; identify all exclusions.
- Schedule showing earliest start, total duration, key milestones, inspections and final restoration.

- Identification of the Oregon-licensed civil engineer responsible for preparing sealed construction plans; proposed design, agency review and permit schedule; list of required permits and approvals; and subcontractors. Contractor retains full responsibility for obtaining approved civil plans, delivering approved copies to HALC, and securing all required permits.
- Proof of insurance and bonding capability; express acknowledgment of Davis-Bacon prevailing wage, certified payroll and federal labor standards requirements.

## 5. Procurement, questions and selection

**A site walkthrough is required. Proposals submitted without a site visit will not be considered. Contact Dan Butler @ 541-265-5326 X 312 or by email, dbutler@housinglincolncountyor.gov to schedule site visits**

All other questions and proposals shall be submitted to **Dan Butler, dbutler@housinglincolncountyor.gov.**

**Submit proposals by 5pm November 25, 2026**

HALC may request clarifications, negotiate allowable terms, reject any or all proposals, or award based on qualifications, approach, price, schedule and best overall value, subject to applicable procurement rules.

## 6. Contract administration

Work may begin only following contract execution, all required issued permits, HALC-received approved civil plans and approved submittals and written notice to proceed. All scope changes shall be documented and approved in writing by HALC before additional work is performed. The contractor remains responsible for protection of occupied units and for completion of all required testing, inspections, code-compliant sewer abandonment and restoration.

## Appendix A. Davis-Bacon wage determination reference

Oceanspray Duplexes Sanitary Sewer Replacement is subject to Davis-Bacon wage rates.

Applicable determination: U.S. Department of Labor General Decision OR20260072; Heavy Construction; Modification 1; publication date May 18, 2026.

The contractor shall comply with the full governing wage determination and all applicable Davis-Bacon contract clauses.

"General Decision Number: OR20260072 05/18/2026

State: Oregon

Construction Types: Heavy

Counties: Oregon Counties of Lincoln

Excludes Dredging

| Modification Number | Publication Date |
|---|---|
| 0 | 01/02/2026 |

CARP0096-006 06/01/2025

| | Rates | Fringes |
|---|---|---|
| MILLWRIGHT..... | $ 59.35 | 22.38 |

---

CARP0503-018 06/01/2025

| | Rates | Fringes |
|---|---|---|
| CARPENTER (INCLUDING FORM WORK)..... | $ 53.94 | 16.81 |

---

ELEC0125-002 02/01/2024

| | Rates | Fringes |
|---|---|---|
| LINE CONSTRUCTION: LINEMAN..... | $ 64.17 | 24.54 |

---

ENGI0701-036 01/01/2024

| | Rates | Fringes |
|---|---|---|
| POWER EQUIPMENT OPERATOR GROUP 6 LOADERS: (LESS THAN 1 CU YD.); OILER; GRADE CHECKER; CRANE OILER;FORKLIFT; ROLLER (NON-ASPHALT) ..... | $ 45.81 | 16.90 |
| POWER EQUIPMENT OPERATOR GROUP 5 TRACKHOE/BACKHOE HYDRAULIC: TRACK TYPE UP TO AND INCLUDING 20,000 LBS, WHEEL TYPE (FORD, JOHN DEER, CASE TYPE); BOOM TRUCK OPERATOR; DRILLING: CHURM DRILL AND EARTH BORING MACHINE OPERATOR; DIRECTIONAL DRILL OPERATOR LESS THAN 20,000 LBS PULLBACK; LOADERS, RUBBER TIRED TYPE , LESS THAN 25,00 LBS; FORKLIFT OVER 5 TON, BULLDOZER 20,000 LBS OR 100 HORSES OR LESS; ROLLER; COMPACTOR WITHOUT BLADE..... | $ 49.03 | 16.90 |
| POWER EQUIPMENT OPERATOR GROUP 4 CRANE: HYDRAULIC | | |

CRANE OPERATOR, UNDER 50 TONS; LATTICE BOOM CRANE OPERATOR: LATTICE BOOM CRANE OPERATOR, UNDER 50 TONS; TRACKHOE/BACKHOE-ROBOTIC: TRACK AND WHEEL TYPE, UP TO AND INCLUDING 20,0000 LBS. WITH ANY OR ALL ATTACHMENTS; BLADE: BLADE OPERATOR; TRACTOR OPERATOR WITH BOOM ATTACHMENT; DRILLING: CHURM DRILL AND EARTH BORING MACHINE OPERATOR; DIRECTIONAL DRILL OPERATOR OVER 20,000 LBS PULLBACK; CRANE: CHICAGO BOOM AND SIMILAR TYPES; BOOM TYPE LIFTING DEVICE, 5 TON CAPACITY OR LESS; RUBBER-TIRED SCRAPER, SINGLE ENGINE, SINGLE SCRAPER; COMPACTOR-SELF PROPELLED; LOADERS 25,000 LBS AND LESS THAN 60,000 LBS; BULLDOZER OVER 20,000 LBS AND MORE THAN 100 HORSE UP TO 70,000 LBS; SCREED; COMPACTOR WITH BLADE..... $ 50.27 16.90

POWER EQUIPMENT OPERATOR GROUP 3 HYDRAULIC CRANE: HYDRAULIC CRANE OPERATOR, 50 TONS THROUGH 89 TONS (WITHOUT LUFFING OR TOWER ATTACHMENT); LATTICE BOOM CRANES: LATTICE BOOM CRANE-50 THROUGH 89 TONS (AND LESS THAN 150 FEET BOOM); RUBBER TIRED SCRAPER: WITH TANDOM SCRAPERS; SELF LOADING, PADDLE WHEEL, AUGER TYPE, FINISH AND/OR 2 OR MORE UNITS; LOADER 60,000 LBS AND LESS THAN 120,000 LBS; BULLDOZER OVER 70,000 LBS UP TO AND INCLUDING 120,000 LBS;..... $ 53.60 16.90

POWER EQUIPMENT OPERATOR GROUP 2 CRANE: CABLEWAY OPERATOR, 25 TONS AND OVER; HYDRAULIC CRANE: HYDRAULIC CRANE OPERATOR 90 TONS THROUGH 199 TONS (WITHOUT LUFFING OR TOWER ATTACHMENT); TOWER/WHIRLEY OPERATOR: TOWER CRANE OPERATOR; WHIRLEY OPERATOR, UNDER 90 TONS; LATTICE BOOM CRANE: 90 THROUGH 199 TONS AND/OR 150 TO 200 FEET BOOM; HYDRAULIC CRANE: HYDRAULIC CRANE OPERATOR,

50 TONS THROUGH 89 TONS (WITH LUFFING OR TOWER ATTACHMENT); RUBBER TIRED SCRAPER WITH TANDOM SCRAPERS; LOADER 120,000 LBS AND ABOVE; BLADE: AUTO GRADER; BLADE OPERATOR-ROBOTIC; BULLDOZER OVER 120,000 LBS AND ABOVE;..... $ 54.75 16.90

POWER EQUIPMENT OPERATOR GROUP 1B LATTICE BOOM CRANE: OPERATOR, 300 TONS THROUGH 399 TONS WITH OVER 200 FEET BOOM; OPERATOR 400 TONS AND OVER..... $ 60.98 16.90

POWER EQUIPMENT OPERATOR GROUP 1A HYDRAULIC CRANE: HYDRAULIC OPERATOR, 200 TONS AND OVER (WITH LUFFING OR TOWER ATTACHMENT); LATTICE BOOM CRANE: OPERATOR, 200 TONS THROUGH 299 TONS, WITH OVER 200 FEET BOOM;. $ 58.82 16.90

POWER EQUIPMENT OPERATOR GROUP 1 CRANE: HELICOPTER OPERATOR, WHEN USED IN ERECTING WORK; WHIRLEY OPERATOR, 90 TON AND OVER; LATTICE BOOM CRANE: OPERATOR 200 TONS THROUGH 299 TONS, AND/OR OVER 200 FEET BOOM; HYDRAULIC CRANE: HYDRAULIC CRANE OPERATOR 90 TONS THROUGH 199 TONS WITH LUFFING OR TOWER ATTACHMENTS;..... $ 56.66 16.90

---

ENGI0701-037 01/01/2024

| | Rates | Fringes |
|---|---|---|
| POWER EQUIPMENT OPERATOR:, PIPELINE: GROUP 5 TRACKHOE/BACKHOE HYDRAULIC: TRACK TYPE UP TO AND INCLUDING 20,000 LBS, WHEEL TYPE (FORD, JOHN DEER, CASE TYPE); BULLDOZER 20,000 LBS OR 100 HORSES OR LESS ..... | $ 49.03 | 16.90 |
| POWER EQUIPMENT OPERATOR:, PIPELINE: GROUP 4 TRACKHOE/BACKHOE-ROBOTIC: TRACK AND WHEEL TYPE, UP TO AND INCLUDING 20,0000 LBS. WITH ANY OR ALL ATTACHMENTS; BULLDOZER OVER 20,000 LBS AND MORE THAN 100 HORSE UP TO 70,000 LBS..... | $ 50.27 | 16.90 |

| | | |
|---|---|---|
| POWER EQUIPMENT OPERATOR:, PIPELINE: GROUP 3 | | |
| BULLDOZER OVER 70,000 LBS UP TO AND INCLUDING | | |
| 120,000 LBS;..... | $ 53.60 | 16.90 |
| POWER EQUIPMENT OPERATOR:, PIPELINE: GROUP 2 | | |
| BULLDOZER OVER 120,000 LBS AND ABOVE;..... | $ 54.75 | 16.90 |

---

IRON0029-013 07/07/2025

| | Rates | Fringes |
|---|---|---|
| IRONWORKER (REINFORCING AND STRUCTURAL)..... | $ 48.31 | 34.52 |

---

LABO0737-031 06/01/2024

| | Rates | Fringes |
|---|---|---|
| LABORERS: GROUP 2 GRADE CHECKER..... | $ 40.41 | 17.30 |
| LABORERS: GROUP 1 ASPHALT SPREADER..... | $ 39.11 | 17.30 |

---

PAIN0010-006 07/01/2025

| | Rates | Fringes |
|---|---|---|
| PAINTERS: (BRUSH, ROLLER AND SPRAY)..... | $ 39.94 | 16.68 |

---

PLAS0555-006 06/01/2025

| | Rates | Fringes |
|---|---|---|
| CEMENT MASON/CONCRETE FINISHER..... | $ 46.13 | 20.31 |

---

SUOR2009-070 11/23/2009

| | Rates | Fringes |
|---|---|---|
| TRUCK DRIVER: OFF THE ROAD TRUCK..... | $ 31.81 | 6.33 |
| TRUCK DRIVER: DUMP TRUCK..... | $ 17.22 | 4.83 |
| OPERATOR: PAVER (ASPHALT, AGGREGATE, AND | | |

| | | |
|---|---|---|
| CONCRETE)..... | $ 27.59 | 2.96 |
| OPERATOR: MECHANIC..... | $ 20.64 | 5.58 |
| OPERATOR: EXCAVATOR..... | $ 21.73 | 6.32 |
| OPERATOR: BROOM/SWEEPER..... | $ 32.31 | 6.43 |
| OPERATOR: BOBCAT/SKID STEER/SKID LOADER..... | $ 22.77 | 7.90 |
| LABORER: PIPELAYER..... | $ 18.57 | 6.24 |
| LABORER: MASON TENDER - CEMENT/CONCRETE..... | $ 21.27 | 5.35 |
| LABORER: FLAGGER..... | $ 18.76 | 6.15 |
| LABORER: COMMON OR GENERAL..... | $ 21.43 | 7.76 |
| ELECTRICIAN..... | $ 29.90 | 11.92 |

---

TEAM0037-012 06/01/2025

| | Rates | Fringes |
|---|---|---|
| TRUCK DRIVER GROUP 4 WATER TRUCK OVER 10,000 TO 15,000 GALLONS..... | $ 36.08 | 18.30 |
| TRUCK DRIVER GROUP 3 WATER TRUCK OVER 5,000 TO 10,000 GALLONS..... | $ 35.74 | 18.30 |
| TRUCK DRIVER GROUP 2 WATER TRUCK OVER 3,000 TO 5,000 GALLONS..... | $ 35.57 | 18.30 |
| TRUCK DRIVER GROUP 1 WATER TRUCK UP TO 3,000 GALLONS..... | $ 35.41 | 18.30 |

---

---

WELDERS - Receive rate prescribed for craft performing operation to which welding is incidental.

==========

Note: Executive Order (EO) 13706, Establishing Paid Sick Leave for Federal Contractors applies to all contracts subject to the Davis-Bacon Act for which the contract is awarded (and any solicitation was issued) on or after January 1, 2017. If this contract is covered by the EO, the contractor must provide

employees with 1 hour of paid sick leave for every 30 hours they work, up to 56 hours of paid sick leave each year. Employees must be permitted to use paid sick leave for their own illness, injury or other health-related needs, including preventive care; to assist a family member (or person who is like family to the employee) who is ill, injured, or has other health-related needs, including preventive care; or for reasons resulting from, or to assist a family member (or person who is like family to the employee) who is a victim of, domestic violence, sexual assault, or stalking. Additional information on contractor requirements and worker protections under the EO is available at https://www.dol.gov/agencies/whd/government-contracts.

Note: Executive Order 13658 generally applies to contracts subject to the Davis-Bacon Act that were awarded on or between January 1, 2015 and January 29, 2022, and that have not been renewed or extended on or after January 30, 2022. Executive Order 13658 does not apply to contracts subject only to the Davis-Bacon Related Acts regardless of when they were awarded. If a contract is subject to Executive Order 13658, the contractor must pay all covered workers at least $13.65 per hour (or the applicable wage rate listed on this wage determination, if it is higher) for all hours spent performing on the contract from May 11, 2026, through December 31, 2026. The applicable Executive Order minimum wage rate will be adjusted annually. Additional information on contractor requirements and worker protections under Executive Order 13658 is available at www.dol.gov/whd/govcontracts.

Unlisted classifications needed for work not included within the scope of the classifications listed may be added after award only as provided in the labor standards contract clauses (29CFR 5.5 (a) (1) (iii)).

---

The body of each wage determination lists the classifications and wage rates that have been found to be prevailing for the type(s) of construction and geographic area covered by the wage determination. The classifications are listed in alphabetical order under rate identifiers indicating whether the particular rate is a union rate (current union negotiated rate), a survey rate, a weighted union average rate, a state adopted rate, or a supplemental classification rate.

Union Rate Identifiers

A four-letter identifier beginning with characters other than SU , UAVG , SA , or SC denotes that a union rate was prevailing for that classification in the survey. Example: PLUM0198-005 07/01/2024. PLUM is an identifier of the union whose collectively bargained rate prevailed in the survey for this classification, which in this example would be Plumbers. 0198 indicates the local union number or district council number where applicable, i.e., Plumbers Local 0198. The next number, 005 in the example, is an internal number used in processing the wage determination. The date, 07/01/2024 in the example, is the effective date of the most current negotiated rate.

Union prevailing wage rates are updated to reflect all changes over time that are reported to WHD in the rates in the collective bargaining agreement (CBA) governing the classification.

Union Average Rate Identifiers

The UAVG identifier indicates that no single rate prevailed for those classifications, but that 100% of the data reported for

the classifications reflected union rates. EXAMPLE: UAVG-OH-0010 01/01/2024. UAVG indicates that the rate is a weighted union average rate. OH indicates the State of Ohio. The next number, 0010 in the example, is an internal number used in producing the wage determination. The date, 01/01/2024 in the example, indicates the date the wage determination was updated to reflect the most current union average rate.

A UAVG rate will be updated once a year, usually in January, to reflect a weighted average of the current rates in the collective bargaining agreements on which the rate is based.

Survey Rate Identifiers

The SU identifier indicates that either a single non-union rate prevailed (as defined in 29 CFR 1.2) for this classification in the survey or that the rate was derived by computing a weighted average rate based on all the rates reported in the survey for that classification. As a weighted average rate includes all rates reported in the survey, it may include both union and non-union rates. Example: SUFL2022-007 6/27/2024. SU indicates the rate is a single non-union prevailing rate or a weighted average of survey data for that classification. FL indicates the State of Florida. 2022 is the year of the survey on which these classifications and rates are based. The next number, 007 in the example, is an internal number used in producing the wage determination. The date, 6/27/2024 in the example, indicates the survey completion date for the classifications and rates under that identifier.

SU wage rates typically remain in effect until a new survey is conducted. However, the Wage and Hour Division (WHD) has the discretion to update such rates under 29 CFR 1.6(c)(1).

State Adopted Rate Identifiers

The SA identifier indicates that the classifications and prevailing wage rates set by a state (or local) government were adopted under 29 C.F.R 1.3(g)-(h). Example: SAME2023-007 01/03/2024. SA reflects that the rates are state adopted. ME refers to the State of Maine. 2023 is the year during which the state completed the survey on which the listed classifications and rates are based. The next number, 007 in the example, is an internal number used in producing the wage determination. The date, 01/03/2024 in the example, reflects the date on which the classifications and rates under the SA identifier took effect under state law in the state from which the rates were adopted.

---

WAGE DETERMINATION APPEALS PROCESS

1) Has there been an initial decision in the matter? This can be:

a) a survey underlying a wage determination

b) an existing published wage determination

c) an initial WHD letter setting forth a position on a wage determination matter

d) an initial conformance (additional classification and rate) determination

On survey related matters, initial contact, including requests for summaries of surveys, should be directed to the WHD Branch of Wage Surveys. Requests can be submitted via email to davisbaconinfo@dol.gov or by mail to:

Branch of Wage Surveys
Wage and Hour Division
U.S. Department of Labor
200 Constitution Avenue, N.W.

Washington, DC 20210

Regarding any other wage determination matter such as conformance decisions, requests for initial decisions should be directed to the WHD Branch of Construction Wage Determinations. Requests can be submitted via email to BCWD-Office@dol.gov or by mail to:

Branch of Construction Wage Determinations
Wage and Hour Division
U.S. Department of Labor
200 Constitution Avenue, N.W.
Washington, DC 20210

2) If an initial decision has been issued, then any interested party (those affected by the action) that disagrees with the decision can request review and reconsideration from the Wage and Hour Administrator (See 29 CFR Part 1.8 and 29 CFR Part 7). Requests for review and reconsideration can be submitted via email to dba.reconsideration@dol.gov or by mail to:

Wage and Hour Administrator
U.S. Department of Labor
200 Constitution Avenue, N.W.
Washington, DC 20210

The request should be accompanied by a full statement of the interested party's position and any information (wage payment data, project description, area practice material, etc.) that the requestor considers relevant to the issue.

3) If the decision of the Administrator is not favorable, an interested party may appeal directly to the Administrative Review Board (formerly the Wage Appeals Board). Write to:

Administrative Review Board
U.S. Department of Labor
200 Constitution Avenue, N.W.
Washington, DC 20210.

==========

END OF GENERAL DECISION"